

PREFABRICATED TOWERS

Guardrails are fabricated in fully welded panels for strength and ease of installation.
(3-Railed public access design shown in this illustration)

All assembly hardware provided, preventing unnecessary trips to the hardware store.

All framing members are structural steel tubes and beams, not flimsy cold formed sections.

Fully Braced Structure, designed to resist the most extreme conditions.

All angles and clips used to connect structural components are factory welded in place to dramatically enhance the speed of on-site assembly.



Harrelson Modular Towers are designed to be fully integrated with Harrelson Modular Prefabricated Buildings.

Landings are cantilevered to maximize space around the perimeter of the tower.

Factory Welded Stairs, providing one step installation instead of full field assembly of components.